Eaton 172837

Eaton Moeller® series P3 Main switch, P3, 100 A, rear mounting, 3 pole

Eaton Moeller® series P3 Main switch
172837
82 mm
84 mm
72 mm
0.29 kg
UL Category Control No.: NLRV IEC/EN 60947-3 CSA UL File No.: E36332 UL CE IEC/EN 60947 IEC/EN 60947 IEC/EN 60204 CSA-C22.2 No. 94 CSA Class No.: 3211-05 CSA File No.: 012528 CSA-C22.2 No. 60947-4-1-14 VDE 0660 UL 60947-4-1
Rated Short-time Withstand Current (Icw) for a time of 1 second



PRODUCT CATEGORY	Main switch
FEATURES	Version as main switch
ACTUATOR COLOR	Other
10.10 TEMPERATURE RISE	The panel builder is responsible for the temperature rise calculation. Eaton will provide heat dissipation data for the devices.
10.11 SHORT-CIRCUIT RATING	Is the panel builder's responsibility. The specifications for the switchgear must be observed.
10.12 ELECTROMAGNETIC COMPATIBILITY	Is the panel builder's responsibility. The specifications for the switchgear must be observed.
10.13 MECHANICAL FUNCTION	The device meets the requirements, provided the information in the instruction leaflet (IL) is observed.
10.2.2 CORROSION RESISTANCE	Meets the product standard's requirements.
10.2.3.1 VERIFICATION OF THERMAL STABILITY OF ENCLOSURES	Meets the product standard's requirements.
10.2.3.2 VERIFICATION OF RESISTANCE OF INSULATING MATERIALS TO NORMAL HEAT	Meets the product standard's requirements.
10.2.3.3 RESIST. OF INSUL. MAT. TO ABNORMAL HEAT/FIRE BY INTERNAL ELECT. EFFECTS	Meets the product standard's requirements.
10.2.4 RESISTANCE TO ULTRA-VIOLET (UV) RADIATION	UV resistance only in connection with protective shield.
10.2.5 LIFTING	Does not apply, since the entire switchgear needs to be evaluated.
10.2.6 MECHANICAL IMPACT	Does not apply, since the entire switchgear needs to be evaluated.
10.2.7 INSCRIPTIONS	Meets the product standard's requirements.

eaton-switch- disconnector-p3-metal- shaft-il008009zu.pdf
eaton-rotary-switches-on- off-switch-p3-main-switch- wiring-diagram.eps
eaton-rotary-switches- front-plate-t0-on-off- switch-symbol-002.eps

10.3 DEGREE OF PROTECTION OF ASSEMBLIES 10.4 CLEARANCES AND CREEPAGE DISTANCES 10.5 PROTECTION AGAINST ELECTRIC SHOCK 10.6 INCORPORATION OF SWITCHING DEVICES AND COMPONENTS 10.7 INTERNAL ELECTRICAL CIRCUITS AND CONNECTIONS 10.8 CONNECTIONS 10.9.2 POWER- FREQUENCY ELECTRIC STRENGTH 10.9.3 IMPULSE WITHSTAND VOLTAGE CLIMATIC PROOFING RATED IMPULSE WITHSTAND VOLTAGE University of the entire switchgear needs to be evaluated. Does not apply, since the entire switchgear needs to be evaluated. Does not apply, since the entire switchgear needs to be evaluated. Is the panel builder's responsibility. In 10.9.4 TESTING OF ENCLOSURES MADE OF INSULATING MATERIAL OPERATING FREQUENCY POLLUTION DEGREE 3 Damp heat, constant, to IEC 60068-2-78 Damp heat, cyclic, to IEC 60068-2-30 RATED IMPULSE WITHSTAND VOLTAGE (UIMP) RATED PERMANENT CURRENT AT AC-21, 400 V 100 A	10.3 DEGREE OF	Does not apply since the
CREEPAGE DISTANCES 10.5 PROTECTION AGAINST ELECTRIC SHOCK 10.6 INCORPORATION OF SWITCHING DEVICES AND COMPONENTS 10.7 INTERNAL ELECTRICAL CIRCUITS AND CONNECTIONS 10.8 CONNECTIONS FOR EXTERNAL CONDUCTORS 10.9.2 POWER- FREQUENCY ELECTRIC STRENGTH 10.9.3 IMPULSE WITHSTAND VOLTAGE OPERATING FREQUENCY POLLUTION DEGREE CLIMATIC PROOFING RATED IMPULSE WITHSTAND VOLTAGE WITHSTAND VOLTAGE WITHSTAND VOLTAGE CLIMATIC PROOFING RATED IMPULSE WITHSTAND VOLTAGE WITHSTAND VOLTAGE OPERATING OF ENCLOSURES MADE OF INSULATION DEGREE ADAMP heat, constant, to IEC 60068-2-78 Damp heat, cyclic, to IEC 60068-2-30 RATED IMPULSE WITHSTAND VOLTAGE WITHSTAND VOL		entire switchgear needs to
AGAINST ELECTRIC SHOCK 10.6 INCORPORATION OF SWITCHING DEVICES AND COMPONENTS 10.7 INTERNAL ELECTRICAL CIRCUITS AND CONNECTIONS 10.8 CONNECTIONS FOR EXTERNAL CONDUCTORS 10.9.2 POWER- FREQUENCY ELECTRIC STRENGTH 10.9.3 IMPULSE WITHSTAND VOLTAGE 10.9.4 TESTING OF ENCLOSURES MADE OF INSULATING MATERIAL OPERATING FREQUENCY POLLUTION DEGREE CLIMATIC PROOFING RATED IMPULSE WITHSTAND VOLTAGE WITHSTAND VOLTAGE CLIMATIC PROOFING RATED IMPULSE WITHSTAND VOLTAGE WITHSTAND VOLTAGE OBM Device we entire switchgear needs to be evaluated. Does not apply, since the entire switchgear needs to be evaluated. Dies not apply, since the entire switchgear needs to be evaluated. Is the panel builder's responsibility.		•
SWITCHING DEVICES AND COMPONENTS 10.7 INTERNAL ELECTRICAL CIRCUITS AND CONNECTIONS 10.8 CONNECTIONS FOR EXTERNAL CONDUCTORS 10.9.2 POWER- FREQUENCY ELECTRIC STRENGTH 10.9.3 IMPULSE WITHSTAND VOLTAGE 10.9.4 TESTING OF ENCLOSURES MADE OF INSULATING MATERIAL OPERATING FREQUENCY POLLUTION DEGREE CLIMATIC PROOFING RATED IMPULSE WITHSTAND VOLTAGE WITHSTAND VOLTAGE CLIMATIC PROOFING entire switchgear needs to be evaluated. Is the panel builder's responsibility.	AGAINST ELECTRIC	entire switchgear needs to
ELECTRICAL CIRCUITS AND CONNECTIONS 10.8 CONNECTIONS FOR EXTERNAL CONDUCTORS 10.9.2 POWER- FREQUENCY ELECTRIC STRENGTH 10.9.3 IMPULSE WITHSTAND VOLTAGE 10.9.4 TESTING OF ENCLOSURES MADE OF INSULATING MATERIAL OPERATING FREQUENCY POLLUTION DEGREE CLIMATIC PROOFING RATED IMPULSE WITHSTAND VOLTAGE UIMP) RATED PERMANENT Is the panel builder's responsibility. Is the panel builder's responsibility. Is the panel builder's responsibility. Damp heat, constant, to IEC 60068-2-78 Damp heat, cyclic, to IEC 60068-2-30 RATED IMPULSE WITHSTAND VOLTAGE (UIMP) RATED PERMANENT 100 A	SWITCHING DEVICES AND	entire switchgear needs to
TO.9.2 POWER-FREQUENCY ELECTRIC STRENGTH 10.9.3 IMPULSE Is the panel builder's responsibility. 10.9.4 TESTING OF ENCLOSURES MADE OF INSULATING MATERIAL OPERATING FREQUENCY POLLUTION DEGREE CLIMATIC PROOFING CLIMATIC PROOFING RATED IMPULSE Is the panel builder's responsibility. Is the panel builder's responsibility. Is the panel builder's responsibility. Damp heat builder's responsibility. 1200 Operations/h Damp heat, constant, to IEC 60068-2-78 Damp heat, cyclic, to IEC 60068-2-30 RATED IMPULSE WITHSTAND VOLTAGE (UIMP) RATED PERMANENT 100 A	ELECTRICAL CIRCUITS	·
FREQUENCY ELECTRIC STRENGTH 10.9.3 IMPULSE WITHSTAND VOLTAGE 10.9.4 TESTING OF ENCLOSURES MADE OF INSULATING MATERIAL OPERATING FREQUENCY POLLUTION DEGREE CLIMATIC PROOFING CLIMATIC PROOFING RATED IMPULSE WITHSTAND VOLTAGE (UIMP) RATED PERMANENT Is the panel builder's responsibility. Is the panel builder's responsibility. Damp load, constant, to IEC 60068-2-78 Damp heat, cyclic, to IEC 60068-2-30 RATED IMPULSE WITHSTAND VOLTAGE (UIMP) RATED PERMANENT 100 A		•
WITHSTAND VOLTAGE 10.9.4 TESTING OF ENCLOSURES MADE OF INSULATING MATERIAL OPERATING FREQUENCY POLLUTION DEGREE CLIMATIC PROOFING Damp heat, constant, to IEC 60068-2-78 Damp heat, cyclic, to IEC 60068-2-30 RATED IMPULSE WITHSTAND VOLTAGE (UIMP) RATED PERMANENT 100 A	FREQUENCY ELECTRIC	·
ENCLOSURES MADE OF INSULATING MATERIAL OPERATING FREQUENCY POLLUTION DEGREE CLIMATIC PROOFING Damp heat, constant, to IEC 60068-2-78 Damp heat, cyclic, to IEC 60068-2-30 RATED IMPULSE WITHSTAND VOLTAGE (UIMP) RATED PERMANENT Is the panel builder's responsibility. 1200 Operations/h 6000 Frequency 1200 Operations/h 1200 Operations/h 6000 V AC		•
POLLUTION DEGREE CLIMATIC PROOFING Damp heat, constant, to IEC 60068-2-78 Damp heat, cyclic, to IEC 60068-2-30 RATED IMPULSE WITHSTAND VOLTAGE (UIMP) RATED PERMANENT 100 A	ENCLOSURES MADE OF	·
CLIMATIC PROOFING Damp heat, constant, to IEC 60068-2-78 Damp heat, cyclic, to IEC 60068-2-30 RATED IMPULSE WITHSTAND VOLTAGE (UIMP) RATED PERMANENT 100 A	OPERATING FREQUENCY	1200 Operations/h
CLIMATIC PROOFING IEC 60068-2-78 Damp heat, cyclic, to IEC 60068-2-30 RATED IMPULSE WITHSTAND VOLTAGE (UIMP) RATED PERMANENT 100 A	POLLUTION DEGREE	3
WITHSTAND VOLTAGE 6000 V AC (UIMP) RATED PERMANENT 100 A	CLIMATIC PROOFING	IEC 60068-2-78 Damp heat, cyclic, to IEC
100 A	WITHSTAND VOLTAGE	6000 V AC
		100 A
RATED PERMANENT CURRENT AT AC-23, 400 V		100 A
RATED UNINTERRUPTED CURRENT (IU) 100 A		100 A
STATIC HEAT	STATIC HEAT DISSIPATION, NON- CURRENT-DEPENDENT PVS	0 W
CURRENT-DEPENDENT	SWITCHING POWER AT 400 V	55 kW
CURRENT-DEPENDENT PVS SWITCHING POWER AT 55 kW	VOLTAGE PER CONTACT PAIR IN SERIES	60 V
CURRENT-DEPENDENT PVS SWITCHING POWER AT 400 V VOLTAGE PER CONTACT 60 V	ACCESSORIES	Auxiliary contact or neutral conductor fitted by

	user.
DEVICE CONSTRUCTION	Built-in device fixed built- in technique
RATED SHORT-TIME WITHSTAND CURRENT (ICW)	2 kA
ELECTRICAL CONNECTION TYPE OF MAIN CIRCUIT	Screw connection
MOUNTING POSITION	As required
ACTUATOR TYPE	Other
AMBIENT OPERATING TEMPERATURE - MAX	50 °C
AMBIENT OPERATING TEMPERATURE - MIN	-25 °C
AMBIENT OPERATING TEMPERATURE (ENCLOSED) - MAX	40 °C
AMBIENT OPERATING TEMPERATURE (ENCLOSED) - MIN	-25 °C
ASSIGNED MOTOR POWER AT 115/120 V, 60 HZ, 1-PHASE	5 HP
ASSIGNED MOTOR POWER AT 200/208 V, 60 HZ, 1-PHASE	10 HP
ASSIGNED MOTOR POWER AT 200/208 V, 60 HZ, 3-PHASE	20 HP
ASSIGNED MOTOR POWER AT 230/240 V, 60 HZ, 1-PHASE	15 HP
ASSIGNED MOTOR POWER AT 230/240 V, 60 HZ, 3-PHASE	25 HP
ASSIGNED MOTOR POWER AT 460/480 V, 60 HZ, 3-PHASE	60 HP
ASSIGNED MOTOR POWER AT 575/600 V, 60 HZ, 3-PHASE	75 HP
EQUIPMENT HEAT DISSIPATION, CURRENT- DEPENDENT PVID	0 W
HEAT DISSIPATION CAPACITY PDISS	0 W
HEAT DISSIPATION PER POLE, CURRENT-	7.5 W

DEPENDENT PVID	
NUMBER OF AUXILIARY CONTACTS (CHANGE- OVER CONTACTS)	0
NUMBER OF AUXILIARY CONTACTS (NORMALLY CLOSED CONTACTS)	0
RATED CONDITIONAL SHORT-CIRCUIT CURRENT (IQ)	4 kA (Load side) 80 kA (Supply side)
OVERVOLTAGE CATEGORY	III
CONTROL CIRCUIT RELIABILITY	1 failure per 100,000 switching operations statistically determined, at 24 V DC, 10 mA)
DEGREE OF PROTECTION (FRONT SIDE)	IP65
NUMBER OF POLES	3
MOUNTING METHOD	Rear mounting
DEGREE OF PROTECTION	NEMA 1
SUITABLE FOR	Intermediate mounting Ground mounting Branch circuits, suitable as motor disconnect, (UL/CSA)
NUMBER OF SWITCHES	1
SAFE ISOLATION	440 V AC, Between the contacts, According to EN 61140
SCREW SIZE	M5, Terminal screw
	-,
SHOCK RESISTANCE	15 g, Mechanical, According to IEC/EN 60068-2-27, Half- sinusoidal shock 20 ms
SHOCK RESISTANCE LIFESPAN, MECHANICAL	15 g, Mechanical, According to IEC/EN 60068-2-27, Half-
	15 g, Mechanical, According to IEC/EN 60068-2-27, Half- sinusoidal shock 20 ms
LIFESPAN, MECHANICAL	15 g, Mechanical, According to IEC/EN 60068-2-27, Half- sinusoidal shock 20 ms 100,000 Operations 2 x l _e (with intermittent operation class 12, 25 % duty factor) 1.3 x l _e (with intermittent operation class 12, 60 % duty factor) 1.6 x l _e (with intermittent operation class 12, 40 %

(AUXILIARY CONTACTS, PILOT DUTY)	A600 (UL/CSA)
TERMINAL CAPACITY	2 x (2.5 - 10) mm ² , solid or stranded 1 x (1.5 - 25) mm ² , flexible with ferrules to DIN 46228 2 x (1.5 - 6) mm ² , flexible with ferrules to DIN 46228 1 x (2.5 - 35) mm ² , solid or stranded 14 - 2 AWG, solid or flexible with ferrule
SWITCHING CAPACITY (MAIN CONTACTS, GENERAL USE)	100 A, If used with neutral conductor IU = max. 90 A, Rated uninterrupted current max. (UL/CSA)
SAFETY PARAMETER (EN ISO 13849-1)	B10d values as per EN ISO 13849-1, table C.1
NUMBER OF AUXILIARY CONTACTS (NORMALLY OPEN CONTACTS)	0
NUMBER OF CONTACTS IN SERIES AT DC-23A, 120 V	3
NUMBER OF CONTACTS IN SERIES AT DC-23A, 24 V	1
NUMBER OF CONTACTS IN SERIES AT DC-23A, 48 V	2
NUMBER OF CONTACTS IN SERIES AT DC-23A, 60 V	2
RATED BREAKING CAPACITY AT 220/230 V (COS PHI TO IEC 60947-3)	760 A
RATED BREAKING CAPACITY AT 400/415 V (COS PHI TO IEC 60947-3)	740 A
RATED BREAKING CAPACITY AT 500 V (COS PHI TO IEC 60947-3)	880 A
RATED BREAKING CAPACITY AT 660/690 V (COS PHI TO IEC 60947-3)	520 A
RATED MAKING CAPACITY UP TO 690 V (COS PHI TO IEC/EN 60947-3)	950 A
RATED OPERATING VOLTAGE (UE) - MAX	690 V
RATED OPERATING VOLTAGE (UE) - MIN	690 V

RATED OPERATIONAL VOLTAGE (UE) AT AC - MAX	690 V
SHORT-CIRCUIT CURRENT RATING (BASIC RATING)	150A, max. Fuse, SCCR (UL/CSA) 10 kA, SCCR (UL/CSA)
SHORT-CIRCUIT PROTECTION RATING	100 A gG/gL, Fuse, Contacts
RATED OPERATIONAL CURRENT (IE) AT AC-21, 440 V	100 A
RATED OPERATIONAL CURRENT (IE) AT AC-23A, 230 V	100 A
RATED OPERATIONAL CURRENT (IE) AT AC-23A, 400 V, 415 V	100 A
RATED OPERATIONAL CURRENT (IE) AT AC-23A, 500 V	96 A
RATED OPERATIONAL CURRENT (IE) AT AC-23A, 690 V	68 A
RATED OPERATIONAL CURRENT (IE) AT AC-3, 220 V, 230 V, 240 V	71 A
RATED OPERATIONAL CURRENT (IE) AT AC-3, 380 V, 400 V, 415 V	71 A
RATED OPERATIONAL CURRENT (IE) AT AC-3, 500 V	65 A
RATED OPERATIONAL CURRENT (IE) AT AC-3, 660 V, 690 V	23.8 A
RATED OPERATIONAL CURRENT (IE) AT DC-1, LOAD-BREAK SWITCHES L/R = 1 MS	100 A
RATED OPERATIONAL CURRENT (IE) AT DC-23A, 120 V	25 A
RATED OPERATIONAL CURRENT (IE) AT DC-23A, 24 V	50 A
RATED OPERATIONAL CURRENT (IE) AT DC-23A, 48 V	50 A
RATED OPERATIONAL CURRENT (IE) AT DC-23A,	50 A

60 V	
RATED OPERATIONAL CURRENT FOR SPECIFIED HEAT DISSIPATION (IN)	100 A
RATED OPERATIONAL POWER AT AC-23A, 220/230 V, 50 HZ	30 kW
RATED OPERATIONAL POWER AT AC-23A, 400 V, 50 HZ	55 kW
RATED OPERATIONAL POWER AT AC-23A, 500 V, 50 HZ	55 kW
RATED OPERATIONAL POWER AT AC-23A, 690 V, 50 HZ	55 kW
RATED OPERATIONAL POWER AT AC-3, 380/400 V, 50 HZ	37 kW
RATED OPERATIONAL POWER AT AC-3, 415 V, 50 HZ	37 kW
RATED OPERATIONAL POWER AT AC-3, 690 V, 50 HZ	37 kW
TIGHTENING TORQUE	26.5 lb-in, Screw terminals 3 Nm, Screw terminals
UNINTERRUPTED CURRENT	Rated uninterrupted current lu is specified for max. cross-section.

PROJECT NAME:	
PROJECT NUMBER:	
PREPARED BY:	
:	

Plastic



HOUSING MATERIAL

Follow us on social media to get the latest product and support information.











Dublin 4,

Eaton House 30 Pembroke Road